



FERMI Project Overview

M. Svandrlik


14th ESLS RF Workshop

ELETTRA / Trieste, Italy / 2010 September 29 30



Progress over the last 10 years at Elettra

2010



FERMI@Elettra is a 50Hz, single-pass seeded FEL user-facility covering the wavelength range from **100 nm** (12 eV) down to **4 nm** (320 eV)



14th ESLS RF Workshop


ELETTRA / Trieste, Italy / 2010 September 29 30



FERMI@Elettra

Specifications and Performance

Parameter	FEL1	FEL2	Units
Output Wavelength (fundam.)	100 – 20	20 – 4	nm
Output Pulse Length, rms	≤ 50	≤ 50	fs
Peak Power	1 – 5	> 0.3	GW
Photons per Pulse	$> 10^{13}$	$> 10^{12}$	1meV bw
Power Stability	< 30	< 50	%
Transverse Stability	$< 10\%$		e-size
Repetition Rate	10 – 50	50	Hz
Energy	1.2	1.5	GeV
Charge	0.8		nC
Slice Norm. Emittance, rms	1.0		mm mrad
Slice Energy Spread, rms	< 0.20	< 0.15	MeV
Total Energy Spread, rms	< 1.2	< 1.5	MeV
Peak Current, flat region	800		A
Bunch Length, full width	0.7		ps
Energy Jitter, rms	0.1		%
Timing Jitter, rms	< 150		fs




FEL-1 Layout and Commissioning Phases

Phase 1: Jul-Nov '09

Phase 2: Feb-Mar '10


linac tunnel




Phase 3: Jun-Jul '10

Phase 5: Nov-Dec 10: Seeded FEL1 & 1st Basic Experiment

undulator hall



Phase 4: Sept-Oct '10






14th ESLS RF Workshop

ELETTRA / Trieste, Italy / 2010 September 29 30



LINAC layout


FERMI is based on a warm 1.5 GeV linac, made up by 16 S-band accelerating cavities. The accelerator consists of a new high-brightness electron source, a laser heater system for the control of uncorrelated energy spread, a 4th harmonic accelerating section to linearize the bunch charge, and two magnetic bunch compressors to increase the delivered peak current.




14th ESLS RF Workshop




LINAC Sections



INJECTOR
0 – 100MeV



LINAC1 (L01)
100 – 350MeV



LASER HEATER
100MeV



BC1 DIAGS
350MeV



L02 – L04
350 – 1500MeV




14th ESLS RF Workshop

ELETTRA / Trieste, Italy / 2010 September 29 30



Bunch Compressor 1



Compression factor 10 achieved




14th ESLS RF Workshop

ELETTRA / Trieste, Italy / 2010 September 29 30



LINAC, High Power System

The needed RF power for the S-Band plants is provided by 14 Thales TH2132A klystrons (3 GHz, 45 MW peak power in a 4.5 μ sec pulse width) plus a spare klystron that is meant to replace the first two tubes in case of failure. The 12 GHz high power RF source is a scaled version (XL5) of the SLAC XL4 klystron.



LINAC, 3 GHz RF Power Plant (14 are installed)





14th ESLS RF Workshop

ELETTRA / Trieste, Italy / 2010 September 29 30



LINAC Commissioning: on 21.09.2010 attained 1.2 GeV (FEL-1 energy)



Trajectory control and RF phasing are used to maximize the transport efficiency and compensate for the energy loss induced by the linac wake fields.



FEL-1

APPLE-II type undulators allow variable polarization and tunable output wavelength



FEL1 beamline



14th ESLS RF Workshop

ELETTRA / Trieste, Italy / 2010 September 29 30



FERMI Calendar 2010

2010 FERMI@Elettra Beam and Shutdown schedule																
Mezz Month	Gennaio January	Febbraio February	Marzo March	Aprile April	Maggio May	Giugno June	Luglio July	Agosto August	Settembre September	Ottobre October	Novembre November	Dicembre December	Mezz Month			
giorno ITA	date	Shift M; L; N; W	K	date	Shift M; L; N; W	K	date	Shift M; L; N; W	K	date	Shift M; L; N; W	K	date	Shift M; L; N; W	K	week day ENG
L				Installation with beam possible from Linac2 through Main Beam Dump and EH						Installation with beam possible in EH: PADReS and Beamlines				M		
M																T
M																W
G																T
V	1		53													F
S	2															S
D	3															S
L	4	Instal. L1 through BC1 Spectro-meter		1	CoOcc UH		1			2	Install Spreader; FEL-1; MBD		1			M
M	5			2			2			3			2			T
M	6			3			3			4			3			W
G	7			4			4			5			4			T
V	8			5	2nd phase Comm.		5			6			5			F
S	9			6			6			7			6			S
D	10			7			7			8			7			S
L	11			8	L1 through BC1 Spectro-meter		8			9			8			M
M	12			9			9			10			9			T
M	13			10			10			11			10			W
G	14			11			11			12			11			T
V	15			12			12			13			12			F
S	16			13			13			14			13			S
D	17			14			14			15			14			S
L	18			15			15			16			15			M
M	19			16			16			17			16			T
M	20			17			17			18			17			W
G	21			18			18			19			18			T
V	22			19			19			20			19			F
S	23			20			20			21			20			S
D	24			21			21			22			21			S
L	25			22			22			23			22			M
M	26			23			23			24			23			T
M	27			24			24			25			24			W
G	28			25			25			26			25			T
V	29			26			26			27			26			F
S	30			27			27			28			27			S
D	31			28			28			29			28			S
L				29			29			30			29			M
M				30			30			31			30			T
M				31			31						31			W




14th ESLS RF Workshop

ELETTRA / Trieste, Italy / 2010 September 29 - 30



FERMI INTEGRATED INSTALLATION AND COMMISSIONING PLAN		2009												2010												2011											
		1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11	12
Civil Engineering 2008 - 2010																																					
1 st Installation Phase 2009		█																																			
1 st Commissioning Phase 2009														█																							
2 nd Installation Phase 2009-2010														█																							
2 nd Commissioning Phase 2010														█																							
3 rd Installation Phase JAN - JUL 2010														█																							
RUN 3: commiss. BC1 chicane, L2, L3 and L4, TLS and DBD														█																							
4 th Installation Phase JUL-AUG 2010														█																							
RUN 4 Commissioning														█																							
5 th Installation Phase SEP-NOV 2010														█																							
RUN 5: commissioning FEL-1 and PADReS														█																							
Installation of Beamlines and Experimental Stations in EHF														█												█											
FERMI TRANSITION TO OPERATION IN 2011																										█											
6 th Installation Phase DEC 2010 - JAN 2011																										█											
Linac Tunnel and Klystron Gallery	Grouting BC2																									█											
	Collimators: BC1 and TLS (3x)																									█											
	RF Plant KG15 and HERFD																									█											
Undulator Hall	SFEL-2 collimator (1x)																									█											
	Completion of SFEL-2 installation																									█											
	Grouting FEL-2 tables; und. chambers supports																									█											
RUN 6: commissioning, operation and user experiment																										█											
7 th Installation Phase MAR-MAY 2011																										█											
Linac Tunnel and Klystron	X-band accelerating section in linac tunnel																									█											
	X-band RF plant and LLRF in klystron gallery																									█											
Undulator Hall	Bunch Compressor 2 installation																									█											
	Completion of SFEL-2 installation																									█											
RUN 7: commissioning, operation and user experiment																										█											
8 th Installation Phase JUL-AUG 2011																										█											
Undulator hall	FEL-2 undulators and phase shifters installation																									█											
RUN 8: commissioning, operation and user experiment																										█											
Shutdown NOV 2011: maintenance																										█											
RUN 9: commissioning, operation and user experiment																										█											



Conclusion and Outlook

- ❑ FEL-1 installation is almost completed, undulators will come in October.
- ❑ Linac Commissioning is progressing well, **1.2 GeV** energy achieved.
- ❑ Bunch compression factors up to **10** achieved with **BC1**, as expected.
- ❑ Preliminary slice emittance and projected emittance measurements are close to expectations (\sim **1.5 mm mrad** and up to **3 mm mrad** respectively, with a c. f. 6.5).
- ❑ The electron beam has been transported up to the spreader region in the Undulator Hall.
- ❑ Next week beam will be further transported to **FEL-1** and to the **Main Beam Dump** in the Undulator Hall.
- ❑ By end of 2010 we expect the **first lasing with FEL-1** at λ about **60 nm**.
- ❑ During 2011 FEL-2 will be installed, along with FEL-1 optimization and first user experiments.



Acknowledgment

I would like to thank

Simone Di Mitri, Alessandro Fabris, Giuseppe Penco,

Adriana Pertosi and Claudio Serpico

for providing material for this presentation



14th ESLS RF Workshop

ELETTRA / Trieste, Italy / 2010 September 29 30

